



ADDENDUM NO. 1  
TO THE CONTRACT DOCUMENTS

Date: February 19, 2019  
Project No.: 697482

for the construction of  
THREE MILE CREEK SEVERE WEATHER ATTENUATION TANKS (SWATs)

MOBILE AREA WATER AND SEWER SYSTEM  
MOBILE, ALABAMA

**To All Planholders and/or Prospective Bidders:**

The following changes, additions, and/or deletions are hereby made a part of the Contract Documents for the construction of Three Mile Creek Severe Weather Attenuation Tanks (SWATs) dated February 2019 as fully and completely as if the same were fully set forth therein:

**A. PART 3 - SPECIFICATIONS**

1. Section 40 90 01 Supplement 1, Page 16 Subsection "SWAT Fill Sequence", ADD the following:

"During filling operations, when SWAT 1 liquid elevation reaches 47.0, the SWAT 1 influent valve shall close and shall remain closed until the SWAT Drain Sequence has initiated."

**B. DRAWINGS**

1. Drawing 01-G-018, is hereby modified to indicate for SWATs #2 and #3 the top of wall elevation is 50.42 and the Tank Overflow to Sewer elevation is 49.50.
2. Drawing 30-S-202 Key Note 1 is hereby modified to indicate top of concrete is 50.42.
3. Drawing 30-D-302, Section C is hereby modified to indicate the top of the 24" flare is at elevation 49.5.

697482A.GN1

All Bidders shall acknowledge receipt and acceptance of this Addendum No. 1 in the Bid Form and by submitting the Addendum with the bid package. Bid Forms submitted without acknowledgment or without this Addendum will be considered in nonconformance.

CH2M HILL



Project Manager

David Allan Carr, P.E.

**END OF ADDENDUM**